

For your information, we attach photographs showing the typical equipment used for the borehole tests that we want to carry out within your area. The working area for each borehole is typically 15m x 10m (depending on access) and the borehole itself will be approximately 200mm in diameter, with a depth of up to 80 metres. We anticipate that it would take between five and ten days to complete each borehole to the required depth.

A condition survey will be undertaken prior to any work starting with a photographic record. Reinstatement will be agreed with yourselves and a post condition record made to ensure that you are fully satisfied with the work that has been undertaken. **For further information on what to expect in relation to this work please refer to our Code of Practice document attached.**

We would be grateful if you could respond to this letter (to the address above by post or email), giving the contact details of the most appropriate person who we can directly contact to discuss any concerns and particular requirements that you may have, and to arrange a meeting if required.

In the mean time if you have any further queries about this work, please call me on the number given above and I will be happy to explain the proposed works.

Yours faithfully

P.P. Greg. -sole-

Ian Duncan

Thames Tunnel - Geotechnical Manager

*Encl. Borehole Location Plan
 Photos of drill rig
 Code of Practice*

